



Republic of the Philippines
Province of Iloilo
MUNICIPALITY OF CABATUAN

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL BID BULLETIN
ADDENDUM NO.1

**Procurement Materials for the Construction of Electrical Tributary
Line with Rail from Generator Set to Gov't Owned Buildings at
Poblacion, Cabatuan, Iloilo**

Adopted by the BAC during its meeting on March 13, 2023.

Supplemental Bid Bulletin No. 1 is issued to clarify, modify or amend the Bid Documents. This shall form an integral part of the Bid Documents.

References:

Reference: Invitation to Bid				Clarification/Modification/Amendment
Item No.	Qty	Unit	Description	
Lot I – Supply and Delivery of Construction Materials				Lot I – Supply and Delivery of Construction Materials ABC =184,725.00 Bid Doc. Fee : P200.00 Delivery Period- 10 days
Lot II -Supply and delivery Electrical Supplies and 3 units Distribution Transformer 100 KVA				Lot II -Supply and delivery Electrical Supplies ABC=299,055.00 Bid Doc Fee: P500.00 Delivery Period- 25 days
				Lot III-Supply and Delivery of 3 units Distribution Transformer 100 KVA ABC=P945,000.00 Bid Doc Fee: P1,000.00 Delivery Period-25 days
Reference: Technical Specification/Price Schedule or Bill of Quantities				
Lot II- Supply and delivery Electrical Supplies				Lot II- Supply and delivery Electrical Supplies
1	1	pc	Attachment, Guy, Molleable Type w/11/16 Hole Dia.	
2	8	pcs.	Bolt Carriage 3/8" x 4-1/2"	
3	12	pcs.	Bolt, Double Arming 5/8" x 20"	
4	12	pcs.	Bolt, Oval Eye, 5/8" x 9"	
5	2	pcs.	Bolt, Oval Eye, 5/8" x 10"	
6	8	pcs.	Bolt, Machine 1/2" x 6"	

7	3	pcs.	Bolt, Machine 1/2" x 10"	
8	6	pcs.	Bolt, Machine 5/8" x 10"	
9	6	pcs.	Brace, Crossarm, 28" Steel	Thickness=3mm NEA standard, 86 microns 4" x 3"
10	4	pcs.	Brace, Crossarm, 60"-18" Drop (Pair)	
11	6	pcs.	Clamp, Hot Line #6-2/- ACSR	
12	20	pcs.	Clamp, Loop Deadend #2-#2/0 ACSR (U-Bolt)	
13	6	pcs.	Clamp, Deadend Strain #2-#4/0 ACSR	
14	2	pcs.	Clamp, Guy Straight, 3 Bolt Heavy Duty Steel	
15	18	pcs.	Clevis, Secondary Swinging w/o Spool	
16	290	mtrs.	Conductor, Bare, ACSR, #2/0AWG, 6/1 (mtrs)	
17	250	mtrs.	Conductor, Insulated, AAC #2/0. AWG, 6/1 (mtrs)	
18	12	pcs.	Connector, Compression #6-1/0 ACSR Run to #6-#2 (YHO 150)	
19	6	pcs.	Connector, Compression #1-2/0 ACSR Run to #1-#2 (YHO 400)	
20	6	pcs.	Connector, Compression #1-2/0 ACSR Run to #1-#2 (YHO 200)	
21	4	pcs	Connector, Ground Rod (Clamp) For 5/8" Steel Rod	
22	4	pcs	Crossarm, 8ft. Long Galv.	Thickness=3mm NEA standard, 86 microns 4" x 3"
23	4	pcs	Crossarm, 10ft. Long Galv.	
24	3	pcs.	Cutout and Arrester 100 Amps.	
25	2	pcs.	Insulator, Spool Porcelain 1-3/4" G.D ANSI 53-2	
26	15	pcs.	Insulator, Spool Porcelain 3" ANSI 53-4	
27	12	pcs.	Insulator, Suspension Porcelain 3" ANSI 52-1	
28	3	pcs.	Link, Fuse, Universal, Button Head, Type K, 8 Amps.	
29	1	pc.	Meter Box, Steel Const. 14" x 17" x 28"	
30	6	pcs.	Nut Eye 5/8", Conventional	
31	3	pcs.	Pole, Steel, 30ft, Long Galv.	
32	1	pc.	Pole, Steel, 40ft, Long Galv.	
33	1	pc.	Rod, Anchor, Threaded, Single Eye, 5/8" x 7"	
34	4	pcs.	Rod, Ground Steel, Galv. 5/8" x 10"	
35	20	mtrs.	Wire, Guy, Steel, 7/16", 7 Strand (mtr)	
36	20	mtrs.	Control, Insulated Cable, Copper, stranded (#12/4 AWG) mtr	
37	1	pc	Anchor, Concrete, 5" x 5" x 30"	
38	4	rolls	Tape Electrical	Big, 3 meters

				Lot III-Supply and Delivery of 3 units Distribution Transformer 100 KVA
39	3	units	Brand New Distribution Transformer, 100Kva, Amorphous, 120/240V;13200/7620Y, Double Bushing	3 units - Brand New Distribution Transformer, 100Kva, Amorphous, 120/240V;13200/7620Y, Double Bushing
			Warranty: Three years under normal loading	Warranty: Three years under normal loading

For guidance and information of all concerned.


JOSE (NORMAN R. UMADHAY
 BAC Chairperson