



Republic of the Philippines
Province of Iloilo
MUNICIPALITY OF CABATUAN
Tel. No. (033) 522-7861 local 106 /Telefax No. (033) 522-8940

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL BID BULLETIN
ADDENDUM NO.1

Construction of Sewerage System Facility at Cabatuan Public Market
ABC= P 14,892,699.26
Opening of Bid- April 13, 2023 @ 1:30 P.M.
ITB-Infra 2023-03-002

Adopted by the BAC during its meeting on April 4, 2023.

Supplemental Bid Bulletin No. 1 is issued to clarify, modify or amend the Bid Documents. This shall form an integral part of the Bid Documents.

Item No.	References:	Clarification/Amended/Modified
I.	Bid Data Sheet	
ITB Clause		
5.2	Contract similar to the Project refer to contracts which have the same major categories of work Single Largest Completed Contract, SLCC	Bidders must have an experience for the Construction of Sewerage Treatment Facility -Single Largest Completed Contract (SLCC) must be within the last 5 years prior from the opening of bid. -SLCC must be functional during post qualification
10.3	PCAB License and Registration General Building (GB2- Sewerage or Sewage System) Size Range: Medium A Category B	Classification: General Building GB-2 and GB-3 Size Range: at least Small B License Category: C & D Bidder must submit a valid ISO Certificate 9001-2015 during post qualification as part of Technical Specification
15.1	Bid Security	Bid Securing Declaration or Cash or Surety; shall be valid for 120 calendar days from the submission of bids
16	Sealing and Marking of bids	Each bidder shall submit original copy and copy 1 of the first and second components of its bid respectively.
II.	Special Condition of Contract	

GCC Clause				
2				Contract duration –140 Calendar Days to include Saturdays, Sundays , Holidays including the the 20 non-workable days due to unfavorable weather condition The Winning Bidder could ask time extension with justification.
III	Scope of Works			
	Qty	Unit	Scope of Works	
I	1	lot	Temporary Facilities	LGU provides an area for Temporary Facilities to the Winning bidder
II	2	units	Project Billboards and Sign Board	1 unit Project Billboard- 4' x 8' 1 unit COA Billboard – 8' x 8' Made of Wood frame and Plywood or Wood frame and Tarpaulin
III	1	lot	Mobilization/Demobilization	
IV	1	lot	Safety and Health	The Winning Bidder must provide a safety equipment (gear, hardhat, safety shoes, safety gloves, goggles, reflectorized suit, safety harness & etc.) and must have a medicine kit and first aid kit and also provides warning signs/devices.
V	216.20	sq.m.	Demolition of Existing Structure	Old Comfort Room and other obstructions
IX	19.38	cu.m.	Gravel Bedding	On foundation and slab on fill
X	130.94	cu.m.	Concrete Works	For Pump Room and Sedimentation Concrete Mixture (3000 to 3500 psi)- Premix or manual subject to material testing 14, 21 and 28 days Column, Footing, beam, slab, and include Use Gravel 1" , Sand –S1 With Water proofing compound
XI	14,246.16	kgs	Reinforcing Steel	As per plan Columns, Concrete Beams, Floor Slab Included steel requirements; Use Grade 40 for all Deformed Reinforced Steel Bars (12mmØ and 10mmØ Deformed RSB)
XII	679.92	sq.m	Forms Works .	Forms and scaffoldings provided by the Winning Bidder should be claimed by them right after completion of the project Work Accomplishment should proportionate to concrete works
XIII	169.70	sq.m	Plastering Works	Smooth finish for interior and exterior surfaces
XV	200	sq.m	Painting Works (masonry)	Use Boysen or its equivalent
XVI	48.28	sq.m	Painting Works (steel)	Trusses
XVII	102.89	sq.m	Water Proofing (Sedimentation Tank)	Prefer Brand – Bostic or cementous or powermix or better

XXII	503.01	kgs	Structural Steel (Trusses)	As per plan
XXIII	29.92	sq.m	Ceiling (Metal Frame, 4.5mm Fiber Cement Board)	Use 0.3mm x 3m Metal Furring , 4.5mm thick Fiber Cement Board
XXIV	293.22	kgs	Structural Steel (Purlins)	As per plan
XXV	8.8	l.m	Metal Structure (Gutter)	As per plan
XXVI	1	lot	Mechanical Works	Pump and all sewerage system Use Keyword brand or better
XXVII	1	lot	Plumbing Works	Use PPR Pipes and accessories or better for sewerage system facility Use PVC Pipes and accessories or better for sanitary system
XXVIII	1	lot	Electrical Works	Main Panel Board-use G.E brand or better Wire- use THHN stranded cu.wire
XXIX	1	lot	Material Testing	Materials Quality Testing for Aggregates (fine and coarse), Cement, Concrete (6"dia x12") , RSB-(10mm, 12mm,) All testing of materials shall be done by any DPWH Accredited testing centers. Materials tests & laboratory results must conformed with the DPWH standards

- The Winning Bidder should make the premises clean and tidy after the project already completed
- Supplemental Bid Bulletin must be included in the Bid Submission;
- If bidders have Joint Venture Agreement (JVA), bidders must submit Special PCAB License for JVA;
- Single Largest Completed Contract (SLCC) is equivalent to at least 50% of the ABC
- Initial release of 15% as a Mobilization Fee, upon compliance of all pre-release requirements and if they already put up project billboards
- Subsequent releases shall be via progress billing based on project completion duly supported by LGU's accomplishment report and as built plan approved by the LCE.
- Final release of 10% of the contract amount is subject to submission of Certificate of Acceptance by the LGU signifying their acceptance of the fully completed project showing 100% project completion
- Construction Method shall be prepared by the winning bidder upon signing of Contract.
- Water Source and Electricity-the Winning Bidder may opt to connect with LGU providing a sub-meter for consumption reading and to be paid to the Mun. Treasurer's Office of the LGU-Cabatuan.
- Extra Works/Variation Order not exceed 10% of the Contract Price .

For guidance and information of all concerned.


JOSE NORMAN R. UMADHAY
 MGDH/EE Manager
 BAC Chairperson