



Republic of the Philippines
Province of Iloilo
MUNICIPALITY OF CABATUAN
Tel. No. (033) 522-7861 local 106 /Telefax No. (033) 522-8940

BIDS AND AWARDS COMMITTEE

SUPPLEMENTAL BID BULLETIN
ADDENDUM NO.1

IMPROVEMENT OF MANGUNA CHECK DAM AT BRGY. MANGUNA, CABATUAN,
ILOILO

ABC= 5,000,000.00
Opening of Bid: May 23, 2024 @ 2:00 P.M.

Adopted by the BAC during its meeting on May 13, 2024

Supplemental Bid Bulletin No. 1 is issued to clarify, modify or amend the Bid Documents. This shall form an integral part of the Bid Documents.

References: Scope of Works/Technical Specifications/Bill of Quantities				Clarification/Amended/Modified
Item No.	Scope of Works	Qty.	Unit	
A.	Dam Works			
	1.0 Contracts of Camp mobilization and other temporary facilities	1	lot	
	2.0 Diversion of Water and care of creek	1	lot	
	3.0 Dam site (Upstream/downstream)			
	3.1 Demolition works	32	sq.m.	
	3.2 Excavation	129.92	cu.m.	
	3.3 Filter Drain	482.40	kgs	
	3.4 Wooden Control Gate	220	sq.m.	as per plan
	3.5 Collapsible Pier	1152.72	kgs.	as per plan
B	Construction of Retaining Wall			
	1.0 Clearing, Grubbing and Staking	213.60	sq.m.	
	2.0 Excavation	67.0	cu.m.	
	3.0 Concrete Works			
	3.1 Concreting	66.89	cu.m	
	3.2 Steel	3418.50	kgs	
	3.3 Formworks	196	sq.m.	
C	Development of Site			


	1.0 Clearing & Grubbing	242.40	sq.m.	
	2.0 Embankment	360.40	cu.m.	
D	Construction of Pump House			
	1.0 Excavation	12.31	cu.m	
	2.0 Backfilling	10.17	cu.m.	
	3.0 Embankment	14.34	cu.m.	
	4.0 Concrete Works			
	4.1 Concreting	6.58	cu.m	
	4.2 Gravel Bedding	1.30	cu.m.	
	4.3 Steel	719.0	kgs	
	4.4 Formworks	67.48	sq.m.	
	5.0 Steel Works	750.0	kgs	Use No.6 Steel Matting (2"x2") x 4'x8' 2"Øx6m GI Steel Pipe sch 20 1"x1"x1/8" Angle bar
	6.0 Masonry	11.10	sq.m.	Portland Cement- Type I , Low Carbon (Apo/Holcem/Excel) Washed Sand-S1 Gravel-screened 3/4" 4" cured CHB
	7.0 Roofing Works	8.0	sq.m.	as per plan
	8.0 Plastering Works	40.44	sq.m.	smooth finish all surfaces Use mixture 1:2 or 1:1.5
	9.0 Painting Works	12.48	sq.m.	
	10.0 Installation of Pump and Engine set w/ complete accessories	1	lot	see: Technical Requirements for the Installation of Pump & Engine Set with complete accessories (page 38 in the Bidding Documents)
E.	Improvement of Irrigation Canal (Existing)			
	1.0 Clearing and Grubbing	1000	sq.m.	
	2.0 Demolition Works	10.6	sq.m.	
	3.0 Concrete Works			
	3.1 Irrigation Canal			
	3.1.1 Concreting	5.62	cu.m.	
	3.1.2 Steel	25.90	kgs	
	3.1.3 Formworks	2.80	sq.m.	
	3.2 Irrigation Canal (construction)			as per plan
	3.2.1 Concreting	136.90	cu.m.	
	3.2.2 Sub-Base Coarse	28	cu.m.	
	3.2.3 Steel	7212.0	kgs	
	3.2.4 Formworks	1632.0	sq.m	

	3.3 Stilling Pool			
	3.3.1 Concreting	0.84	cu.m.	
	3.3.2 Steel	29.60	kgs	
	3.3.3 Formworks	7.18	sq.m.	
	3.4 Ramp			as per plan
	3.4.1 Concreting	7.05	cu.m.	
	3.4.2 Steel	658.50	kgs	
	3.4.3 Formworks	42.40	sq.m.	
	4.0 Gate Works	2.40	sq.m.	
F.	Project Billboards (1-4'x8' & 1-8'x8')	2	units	2-units 1 unit Project Billboard- 4' x 8' 1 unit COA Billboard – 8' x 8' Made of Wood frame and Plywood or Wood frame and Tarpaulin
XI	Material Testing	1	lot	Materials Quality Testing for Aggregates (fine and coarse), Cement, Concrete, RSB- (10mm,12mm, and 16mm) All testing of materials shall be done by any DPWH Accredited testing centers. Materials tests & laboratory results must conformed with the DPWH standards
	Concreting			use Portland Cement- Type I (Apo/Holcem/Excel) Washed Sand-S1 Gravel-screened ¾"
	Steelworks			16mm RSB-Grade 40 12mm RSB-Grade 33 10mm RSB-Grade 33 No.16 G.I Tie Wire
	Formworks			Forms and scaffoldings provided by the Winning Bidder should be claimed by them right after completion of the project Work Accomplishment should be proportionate to concrete work
ITB Clause	Bid Data Sheet			
10.4	List of Key Personnel must meet the required minimum years of experience			Key Personnel : Project Engineer/Civil Engineer must have at least 2 years experienced in Construction of Dam, Irrigation Canal or similar structures On site: Project Engineer, Safety Officer and Construction Foreman –on site
10.5	The minimum major equipment requirements			

1- Prime Mover 1- Excavator/Breaker 1- Loader/Grader 1- Concrete Mixer 1- Drum Roller/Walk behind roller 1- Jack Hammer 1 Plate Compactor 1 -Standby Gen Set			1 unit- Excavator 1 unit- Loader 1 unit- Concrete Mixer 1 unit –Drum Roller/Walk Behind Roller 1 unit –Jack Hammer 1 unit –Plate Compactor 1 unit – Standby Gen Set
---	--	--	---

- The Bidder shall submit one original copy and copy 1 of the first and second components of its bid respectively.
- Contract duration – 150 Calendar Days to include Saturdays, Sundays, Holidays including the 20 non-workable days due to unfavorable weather condition;
- The winning bidder could ask time extension with justification for non-workable in excess of 20 days;
- The Winning Bidder must provide a safety equipment (gear, hardhat, safety shoes, safety gloves, goggles, reflectorized suit, safety harness & etc.) and must have a medicine kit
- Water and Electricity must be provided by the Winning Bidder;
- The Winning Bidder should make the premises clean and tidy after the project already completed;
- The winning bidder should provide its own generator set;
- Supplemental Bid Bulletin must be included in the Bid Submission;
- If bidders have Joint Venture Agreement (JVA), bidders must submit Special PCAB License for JVA
- Single Largest Completed Contract (SLCC) is equivalent to at least 50% of the ABC;
- Initial release of 15% as a Mobilization Fee, upon compliance of all pre-release requirements and if they already put up project billboards;
- Subsequent releases shall be via progress billing based on project completion duly supported by LGU's accomplishment report and as built plan approved by the LCE;
- Final release of 10% of the contract amount is subject to submission of Certificate of Acceptance by the LGU signifying their acceptance of the fully completed project showing 100% project completion.
- Construction Method shall be prepared by the winning bidder upon signing of Contract.
- Extra Works/Variation Order not exceed 10% of the Contract Price .

For guidance and information of all concerned.


FRANCISCO A. GONZAGA
Municipal Agriculturist
BAC Chairperson